



* INLET: AWWA TAPER ("CC")
 * THREAD OUTLET: F.I.P. THREAD

* ** BACKFLOW PREVENTER TO BE TESTED AFTER INSTALLATION.
 CONTRACTOR TO PROVIDE TEST RESULTS TO INSPECTORS.

- NOTES:
1. REQUIRED AT ALL CONNECTIONS BETWEEN EXISTING ACTIVE WATER MAINS AND PROPOSED WATER MAIN IMPROVEMENTS.
 2. ONLY EXCEPTION TO JUMPER AND METER ASSEMBLY IS INSTALLATION OF FIRE HYDRANT WHERE AN ANCHORING NIPPLE IS USED.



CITY OF COCOA
 Brevard County, Florida
 UTILITIES DEPARTMENT
 ENGINEERING DIVISION

JUMPER METER ASSEMBLY

DRAWN BY: J. WILLIAMS	SCALE: NOT TO SCALE
CHECKED BY: P. DAVIS	DATE: MARCH 2020
DESIGN BY:	SHEET: 1 OF 1
ACAD NAME: JUMPER METER ASSEMBLY	