



NOTE:

1. ASSEMBLY IS TO BE PAINTED RUST-OLEUM 9400 SYSTEM (BLUE) BY THE CITY, PAID FOR BY THE DEVELOPER.
2. ALL ABOVE GROUND NUTS, BOLTS, AND WASHERS TO BE #304 STAINLESS STEEL
3. ALTHREAD ROD WILL NOT BE PERMITTED
4. METER IS TO BE NEPTUNE HIGH PERFORMANCE PROTECTUS III FIRE SERVICE METER WITH STRAINER, PROVIDED BY THE CITY AND PAID BY THE CONTRACTOR.
5. REDUCED PRESSURE BACK FLOW PREVENTER IS TO BE FIRE RATED: FEDCO, AMES, WATTS, CLAS-VAL, WILKINS (ZURN), HERSEY



CITY OF COCOA  
 Brevard County, Florida  
 UTILITIES DEPARTMENT  
 ENGINEERING DIVISION

## MASTER METER ASSEMBLY METER STATION DETAIL

DRAWN BY: J. WILLIAMS	SCALE: NOT TO SCALE
CHECKED BY: P. DAVIS	DATE: MARCH 2020
DESIGN BY:	SHEET: 2 OF 3
ACAD NAME: MASTERMETERASSEMBLY2	