



NOTE:

1. ASSEMBLY IS TO BE PAINTED RUST-OLEUM 9400 SYSTEM (BLUE) BY THE CITY, PAID FOR BY THE DEVELOPER.
2. ALL ABOVE GROUND NUTS, BOLTS, AND WASHERS TO BE #304 STAINLESS STEEL
3. ALTHREAD ROD WILL NOT BE PERMITTED
4. METER IS TO BE NEPTUNE HIGH PERFORMANCE PROTECTUS III FIRE SERVICE METER WITH STRAINER, CITY OF COCOA WILL PROVIDE
5. DOUBLE CHECK VALVE IS TO BE FIRE RATED: FEDCO, AMES, WATTS, CLAS-VAL, WILKINS (ZURN), HERSEY
6. CONCRETE PAD TO BE SAME ELEVATION AS TOP OF EXISTING METER VAULT. MAY REQUIRE FILL MATERIAL

© REFER TO THRUST BLOCK NOTES & DETAILS.



CITY OF COCOA
Brevard County, Florida
UTILITIES DEPARTMENT
ENGINEERING DIVISION

MASTER METER ASSEMBLY DOUBLE CHECK BYPASS

DRAWN BY: J. WILLIAMS	SCALE: NOT TO SCALE
CHECKED BY: P. DAVIS	DATE: MARCH 2020
DESIGN BY:	SHEET: 3 OF 3
ACAD NAME: MASTERMETERASSEMBLY3	